BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

NAME OF THE WORK:-Providing of modern dust bine in Bangalore city in ward no. 07 Byatarayanaura, Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	1.08	KSRRB 2-1.1: Earthwork in surface excvation in ordinary soil for levelling and lowerng the ground manually (other than foundation of buildings, culverts road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exeeding 50m and lift upto 1.5m, excavated stuff to a distance not exceeding 50m and lift upto 1.5m excavated syrface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	cum	166.42	Rupees One Hundred Sixty Six and Forty Two Paise Only
2	0.54	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification .	cum	5159.02	
3	0.54	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine mixed concrete laid in layers not exceeding 15cms thick well compacted in foundation plinth and cills including cost of all materials, labour HOM of machinery curing complete as per specifications	cum	5767.46	
4		Providing and fixing litter bins at selected locations. (Approved rate-approved copy attached)			
5	1.00			31179.14	
6	1.00			34896.14	
7	1.00			29940.14	
8	1.00			32418.14	

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'.

CONTRACTOR

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010